

General Specification for Civil Works - Vol. 2

Project: Proposed G+4 Residential Building

Date: June 14, 2025

Document Ref: PROJ-SPEC-002

1.0 Division 02 - Site Construction & Earthwork

1.1. **Site Clearance:** The entire site area **shall** be cleared of all trees, roots, and any other objectionable matter.

1.2. **Excavation:** Excavation **shall** be carried out to the lines and levels shown on the drawings. Any over-excavation **must** be filled with lean concrete (1:5:10) at the contractor's own cost.

1.3. **Backfilling:** Approved excavated earth **shall** be used for backfilling. Backfilling **is to be** done in layers not exceeding 200mm in thickness, with each layer being properly compacted.

Table 1.1: Soil Compaction Requirements

Location	Minimum Dry Density Required
Under Foundations	98% of MDD*
Under Slabs	95% of MDD*
Landscaped Areas	90% of MDD*

**MDD = Maximum Dry Density as determined by a standard Proctor test.*

2.0 Division 09 - Finishes

2.1. **Internal Plastering:** All internal plastering **shall** be 12mm thick in cement mortar (1:4), finished to a smooth and true surface.

2.2. **Painting:** All internal surfaces **shall** receive one coat of primer and two coats of approved acrylic emulsion paint. The final finish **must** be free of brush marks and uniform in color.

2.3. **Tiling:** Floor tiles **shall** be laid on a 20mm thick cement mortar bed. All tile joints **must** be filled with approved grout and cleaned.

Table 2.1: Approved Paint Brands & Finishes

Location	Paint Type	Finish	Approved Brands
Living Rooms	Premium Emulsion	Matt	Asian Paints, Berger
Kitchens	Washable Emulsion	Satin	Nerolac, Dulux
Bathrooms	Anti-fungal Emulsion	Semi-Gloss	Berger, Asian Paints

End of Document